

15-167-05134-0001

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER N/A Drilled 3-19-50
LEASE NAME Eulert Unit RTCC
WELL NUMBER ~~2310~~

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

2310 Ft. from S Section Line
1650 Ft. from E Section Line
SEC. 35 TWP. 11 RGE. 15 (E) or (W)

LEASE OPERATOR Liedteke Operating Corporation
ADDRESS 370 17th Street, Suite 5020 Denver CO 80202 COUNTY Russell

PHONE# (303) 595-8405 OPERATORS LICENSE NO. 30385

Date Well Completed 5-5-50
Plugging Commenced 10-27-92
Plugging Completed 10-27-92

Character of Well Oil-Injection
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-23-92 (date)
by Don Butcher, Marvin Miller (KCC District Agent's Name).

is ACO-1 filed? N/A If not, is well log attached? N/A

Producing Formation Lans/ K.C. Topeka Depth to Top 3014 Bottom 3238 T.D. 3244

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Topeka				8 5/8	926	None 375 sacks
Lansing				5 1/2"	3334	None 375 sacks

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Pump 70 sacks common 3% CC thru tubing 3244'-2500', pump 100 sacks 60-40 poz 8% gel thru tubing 2500', pump 100 sacks 60-40 poz 8% gel thru tubing 1290', cement circulate in 5 1/2", pull all tubing, pump 145 sacks 60-40 poz thru swage into 5 1/2" casing, 400 PSI - 100 PSI shut in.
Pump 25 sacks 60-40 poz into 8 5/8" 500 PSI - 350 PSI shut in.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Chase Well Service Inc. License No. 6123
Address P.O. Box 355 Great Bend, Kansas 67530


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Liedteke Operating Corporation

STATE OF Kansas COUNTY OF Barton, ss.

Charles W. Steincamp (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) _____
(Address) P.O. Box 355, Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 29th day of October, 1992



Wendy L. Brackeen
Wendy L. Brackeen Notary Public