

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-055-00771-00-00  
Spot: SE Sec/Twnshp/Rge: 22-23S-32W  
1320 feet from S Section Line, 1320 feet from E Section Line  
Lease Name: CRAIN GU Well #: 1  
County: FINNEY Total Vertical Depth: 2700 feet

87.75

Operator License No.: 5952  
Op Name: BP AMERICA PRODUCTION COMPANY  
Address: 2225 W OKLAHOMA AVE  
ULYSSES, KS 67880

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1085		WITH 700 SX CMT
PROD	5.5	2684	0	WITH 800 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/03/2010 11:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: KEVIN STRUBE Company: BP AMERICA Phone: (620) 356-1237

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT Witness Type: NONE  
Date/Time Plugging Completed: 06/03/2010 1:00 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

FILL 5 1/2" WITH CMT FROM 2670' TO 0' USING 75 SX CLASS C CMT, 2% GEL, & 2% CC WITH 200# HULLS FOLLOWED BY 185 SX CMT. PRESSURE TO 500#. HOLDING. PUMP 8 SX CMT DOWN ANNULUS TO 150#. HOLDING.

Perfs:

Top	Bot	Thru	Comments
2664	2700		

INVOICE  
DATE 6/30/10  
INV. NO. 2010061304

RECEIVED  
KANSAS CORPORATION COMMISSION

Remarks: USED CLASS C CMT & 2% GEL.

Plugged through: CSG

JUN 30 2010

CONSERVATION DIVISION  
WICHITA, KS

District: 01

Signed Steve Durrant  
(TECHNICIAN)

RECEIVED  
JUN 22 2010  
KCC DODGE CITY