

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-071-20245-00-00 # 95.23
Spot: SESESE Sec/Twnshp/Rge: 32-19S-40W
270 feet from S Section Line, 312 feet from E Section Line
Lease Name: SPEARS Well #: 1
County: GREELEY Total Vertical Depth: 2930 feet

Operator License No.: 7271
Op Name: BARTLING OIL COMPANY
Address: 1001 CANYON EDGE DR
AUSTIN, TX 78733

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1400		WITH 2 SX CMT
CIBP		2872		
SURF	8.625	290		WITH 225 SX CMT
PROD	4.5	2930	0	WITH 500 SX CMT
RBP		2810		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/27/2010 8:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: GUS OCHSNER Company: BARTLING OIL Phone: (620) 376-2249

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/03/2010 11:30 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

1ST PLUG RBP @ 2810'. 2ND PLUG 4 SX CMT PLUG AT 1757'. 3RD PLUG SET CIBP @ 1400' WITH 2 SX CMT. RAN BOND LOG FROM 1350-100'. TOC @ 380'. 4TH PLUG TESTED CASING TO 700#. PERFORATE AT 350'. ESTABLISH INJECTION RATE. RAN TBG TO 1378' & PUMPED 60 SX CMT. ESTIMATE TOC @ 450'. 5TH PLUG TOO HOOK WITH TBG. HOOK ON TO 4 1/2" & CIRCULATE CMT TO SURFACE FROM 350' WITH 100 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2876	2895		

INVOICED

DATE 6/30/10
INV. NO. 2010061305

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED
JUN 22 2010
KCC DODGE CITY

Signed

Ken Jehlik

RECEIVED
KANSAS CORPORATION COMMISSION
(TECHNICIAN)
JUN 30 2010

CONSERVATION DIVISION
WICHITA, KS

Form CP-273