

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-055-20272-00-01  
Spot: SWNWSESW Sec/Twnshp/Rge: 3-26S-34W  
4539 feet from N Section Line, 1420 feet from W Section Line  
Lease Name: GOVERNMENT Well #: A-1  
County: FINNEY Total Vertical Depth: 2995 feet

\$ 97.34

Operator License No.: 33094  
Op Name: CIMAREX ENERGY CO.  
Address: 15 E 5TH ST STE 1000  
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2734		
SURF	8.625	804		WITH 500 SX CMT
PROD	5.5	2989	0	WITH 675 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/27/2010 10:00 AM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Rcvd. from: KENT PENDERGRAFT Company: CIMAREX ENERGY Phone: (620) 276-3693

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/27/2010 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2734'. PUMP 108 SX CMT FOLLOWED BY 30 BBLs WATER FOR PLUG FROM 1230-2700'. TEST CASING TO 700# FOR 10 MINUTES. PERFORATE @ 850'. CIRCULATE CMT VIA 5 1/2" CASING UP 5 1/2" X 8 5/8" ANNULUS WITH 160 SX CMT. CASING & ANNULUS STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
2786	2877		COUNCIL GROVE

INVOICED  
DATE 6/30/10  
INV. NO. 2010061307

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC CEMENTING.

Plugged through: CSG

District: 01

Signed

*Ken Jehlik*  
(TECHNICIAN)

RECEIVED

JUN 22 2010

KCC DODGE CITY

RECEIVED  
KANSAS CORPORATION COMMISSION Form CP-20

JUN 30 2010

CONSERVATION DIVISION  
WICHITA, KS