

\$ 210.25

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-119-20826-00-02  
Spot: SESESE Sec/Twnshp/Rge: 16-35S-30W  
330 feet from S Section Line, 330 feet from E Section Line  
Lease Name: ADAMS RANCH Well #: 1-16  
County: MEADE Total Vertical Depth: 6470 feet

Operator License No.: 32426  
Op Name: H & L OPERATING CO., L.L.P.  
Address: PO BOX 7506  
AMARILLO, TX 79114

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2850		WITH 10 SX CMT
CIBP		5000		SQUEEZE HOLES @ 3132'
CIBP		6170		
SURF	8.625	1464		WITH 620 SX CMT
PROD	4.5	6449	1510	WITH 350 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/15/2010 10:45 AM  
Plug Co. License No.: 33311 Plug Co. Name: PHIL DOLLAR OILFIELD SERVICES, INC.  
Proposal Rcvd. from: RIGO MONDRANO Company: PHIL DOLLAR OILFIELD SERVICE Phone: (806) 435-3373

Proposed Plugging Method: CIBP @ 2867 & 10 SX CMT. PLUG AT 1500' WITH 75 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 60' WITH 15 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/15/2010 12:00 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

CIBP @ 2850' WITH 10 SX CMT. 1ST PLUG AT 1503' WITH 30 BBLS GEL WATER, 200# HULLS & 75 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
6196	6202		
5705	5715		
2917	2922		

INVOICED  
DATE 6/30/10  
INV. NO. 2010061310

RECEIVED  
KANSAS CORPORATION COMMISSION  
JUN 30 2010  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED CLASS A TYPE 1 CMT BY PHIL DOLLAR OILFIELD SERVICES.

Plugged through: TBG

District: 01

RECEIVED  
JUN 22 2010

Signed Jerry W. Stapleton  
PART II (TECHNICIAN)

KCC DODGE CITY