

7/21. 2B

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-22640-00-00  
Spot: SENENW Sec/Twnshp/Rge: 13-22S-12W  
4290 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: SIEFKES Well #: 2  
County: STAFFORD Total Vertical Depth: 3730 feet

Operator License No.: 32432  
Op Name: LA VETA OIL & GAS, LLC  
Address: 312 N. BUFFALO  
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3588		
SURF	8.625	250		WITH 200 SX CMT
PROD	5.5	3730	0	WITH 150 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/21/2010 8:30 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 3300' & 5 SX CMT. RUN BOND LOG ON TOP PART OF HOLE. CIRCULATE CMT ON HOLE FROM 660' TO SURFACE.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/21/2010 1:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 3301' & 5 SX CMT WITH DUMP BAILER. RAN BOND LOG FINDING CMT AT 1100' TO 290'. PERFORATED 5 1/2" @ 290'. RAN TBG TO 660' & PUMPED 120 SX CMT. CIRCULATED CMT TO SURFACE UP 5 1/2". GOOD BLOW ON 8 5/8" X 5 1/2" ANNULUS BUT NO CMT. PULLED TBG. PUMPED DOWN 5 1/2" WITH 80 SX CMT. LOST CIRCULATION ON 8 5/8" X 5 1/2" ANNULUS. SDON. 6/22/10: PUMPED 95 SX CMT DOWN 5 1/2". PRESSURED TO 500 PSIG & HELD. PUMPED 25 SX CMT DOWN 8 5/8" X 5 1/2" ANNULUS & BLEW A HOLE IN THE 8 5/8".

Perfs:

Top	Bot	Thru	Comments
3346	3577		

INVOICED  
DATE 6/30/10  
INV. NO. 2010061311

RECEIVED  
KANSAS CORPORATION COMMISSION

JUN 30 2010

CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

Signed Richard M. Lacey  
(TECHNICIAN)

RECEIVED

JUN 25 2010

KCC DODGE CITY

Form CP-273