

1159

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-02068-00-00
Spot: E2NWSW Sec/Twnshp/Rge: 29-22S-11W
1980 feet from S Section Line, 990 feet from W Section Line
Lease Name: SPANGENBERG P Well #: 6
County: STAFFORD Total Vertical Depth: 3556 feet

Operator License No.: 32432
Op Name: LA VETA OIL & GAS, LLC
Address: 312 N. BUFFALO
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	10.75	239		WITH 250 SX CMT
PROD 7		3550	0	WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/24/2010 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 3500' & 7 SX CMT. BOND LOG TOP 600' & DETERMINE PROCEDURE.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/24/2010 3:45 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED BOTTOM TO 3500' & 7 SX CMT WITH DUMP BAILER. BOND LOG INDICATED CMT FROM 257'-500'. PERFORATED 7" @ 201'. RAN TBG TO 600'. PUMPED 150 SX CMT CIRCULATING TO SURFACE UP 7". HAD FLOW UP 10 .75" BUT NO CMT. PULLED TBG OUT OF HOLE. PRESSURE 7" TO 500 PSIG WITH 10 SX CMT. COULD NOT ESTABLISH CIRCULATION UP 10 3/4". RAN 1" TBG DOWN 10 3/4" X 7" ANNULUS TO 60'. COULD NOT GET ANY FURTHER. PUMPED 45 SX CMT CIRCULATING IT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3550	3556	OH	

INVOICED
DATE 6/30/10
INV. NO. 2010061311

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 30 2010
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

Signed Richard M. Lacey
(TECHNICIAN)

RECEIVED
JUN 25 2010
KCC DODGE CITY

Form CR-273