

204.75

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-20366-00-00  
Spot: SWSW Sec/Twnshp/Rge: 7-35S-32W  
660 feet from S Section Line, 660 feet from W Section Line  
Lease Name: SMYSER Well #: 1-7  
County: SEWARD Total Vertical Depth: 6300 feet

Operator License No.: 5003  
Op Name: MCCOY PETROLEUM CORPORATION  
Address: 8080 E CENTRAL STE 300  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1523		WITH 750 SX CMT
PROD	4.5	6140	2225	WITH 375 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/01/2010 2:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 6000'. PLUG AT 1550' WITH 20 SX GEL & 50 SX CMT. PLUG AT 500' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/01/2010 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

\*\*CASING LEAKS BETWEEN 2670' & 4477'. TOC @ 4680'\*\* TAGGED TOP OF 2 7/8" TBG FISH @ 5790'. SANDED BACK TO 5700' & 4 SX CMT. 1ST PLUG AT 1550' WITH 20 SX GEL & 50 SX CMT W/200# HULLS. 2ND PLUG AT 500' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6050	6089		

INVOICED  
DATE 6/30/10  
INV. NO. 2010061312

Remarks: USED 60/40 POMZIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: CSG

District: 01

Signed

(TECHNICIAN)  
RECEIVED  
KANSAS CORPORATION COMMISSION

RECEIVED  
JUN 22 2010

KCC DODGE CITY

JUN 30 2010

CONSERVATION DIVISION  
WICHITA, KS

Form CP 273