

#144.69

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-00615-00-00  
Spot: SWSWSE Sec/Twnshp/Rge: 13-18S-26W  
440 feet from S Section Line, 2200 feet from E Section Line  
Lease Name: SHINER Well #: 2  
County: NESS Total Vertical Depth: 4452 feet

Operator License No.: 33190  
Op Name: NOBLE ENERGY, INC.  
Address: 1625 BROADWAY, STE 2200  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	12	207		WITH 235 SX CMT
	11	8		
PROD	6	4436	0	WITH 299 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/17/2010 1:00 PM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Rcvd. from: TOM KARST Company: NOBLE ENERGY Phone: (785) 639-6304

Proposed Plugging Method: RUN TBG TO BOTTOM & CMT, THEN SET HOT PLUG AT 1450'. WAIT ON CMT TO SET UP. TEST CASING. PERFORATE @ 1050' & TRY TO CIRCULATE CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/18/2010 11:45 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

6/17/10: COULD ONLY GET TBG TO 2220'. SPOTTED 50 SX CMT & 100# HULLS. PULLED TBG TO 1450' & SPOTTED 70 SX COMMON CMT W/3% CC. WAITED 1 1/2 HOURS. PRESSURED TO 300# & HELD. PERFORATED AT 1050'. 6/18/10: RUN TBG TO 1060' & PUMPED 150 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & PUMPED 95 SX CMT. CMT CIRCULATED UP BACKSIDE OF CASING. HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
4436	4453		MISSISSIPPIAN/OJ

INVOICED  
DATE 6/30/10  
INV. NO. 2010061315

RECEIVED  
KANSAS CORPORATION COMMISSION

JUN 30 2010

CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed Michael Maier  
(TECHNICIAN)

RECEIVED  
JUN 23 2010  
KCC DODGE CITY