

\$ 138.22

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-22286-00-00  
Spot: NWSENWNW Sec/Twnshp/Rge: 13-24S-14W  
4570 feet from S Section Line, 4570 feet from E Section Line  
Lease Name: ASHER Well #: 1-2  
County: STAFFORD Total Vertical Depth: 4253 feet

Operator License No.: 3911  
Op Name: RAMA OPERATING CO., INC.  
Address: 101 S MAIN ST  
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	362		WITH 225 SX CMT
PLG		4074		
PROD	5.5	4074	2190	WITH 200 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/15/2010 11:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3675' & 5 SX CMT. PLUG AT 840' WITH 10 SX GEL & 50 SX CMT. PLUG AT 390' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX.CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: NONE  
Date/Time Plugging Completed: 06/15/2010 12:30 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 3675' & 5 SX CMT WITH DUMP BAILER. 1ST PLUG AT 840' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 390' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3907	3915		MISS CHT
3724	3814		LKC

INVOICED  
DATE 6/30/10  
INV. NO. 2010061316

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

RECEIVED  
JUN 22 2010  
KCC DODGE CITY

Signed Richard W. Lacey

RECEIVED  
(TECHNICAL) CORPORATION COMMISSION

JUN 30 2010  
CONSERVATION DIVISION  
WICHITA, KS