

\$156.⁹⁸

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22825-00-00
Spot: W2E2E2 Sec/Twnshp/Rge: 32-31S-13W
2640 feet from S Section Line, 910 feet from E Section Line
Lease Name: DUGAN TRUST D Well #: 1
County: BARBER Total Vertical Depth: 4830 feet

Operator License No.: 5046
Op Name: RAYMOND OIL COMPANY, INC.
Address: PO BOX 48788
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	277		250sx
PROD	5.5	4506	2400	300sx

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/24/2010 8:15 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGERSTERN Company: CLARKE CORPORATION Phone: (602) 886-5665

Proposed Plugging Method: 50' ABOVE PERFS SAND & 5 SX CMT. PLUG AT 600' WITH GEL WATER & 50 SX CMT. PLUG AT 240' WITH 75 SX CMT. PLUG AT 40' WITH 25 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE
Date/Time Plugging Completed: 06/24/2010 9:36 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SAND BACK TO 4294' & 5 SX CMT. 1ST PLUG AT 600' WITH 15 SX GELLED WATER & 50 SX CMT. 2ND PLUG AT 240' WITH 75 SX CMT. 3RD PLUG AT 60' WITH 30 SX CMT. CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4344	4364		

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 30 2010
CONSERVATION DIVISION
WICHITA, KS

INVOICED
DATE: 6/30/10
INV. NO. 2010061317

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
JUN 25 2010 *MP*

KCC DODGE CITY

Form CP-278