

\$ 120.09

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-21465-00-00
Spot: N2S2SE Sec/Twnshp/Rge: 25-16S-20W
960 feet from S Section Line, 1320 feet from E Section Line
Lease Name: HART Well #: 1-25
County: RUSH Total Vertical Depth: 3695 feet

Operator License No.: 34004
Op Name: SAXON OIL COMPANY
Address: 5910 N CENTRAL EXPY STE 1250
DALLAS, TX 75206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3498		WITH 2 SX CMT
SURF	8.625	289		WITH 170 SX CMT
DVT		1351		WITH 400 SX CMT
PROD	5.5	3856	0	WITH 550 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/15/2010 11:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: MARK BIEKER Company: SAXON OIL COMPANY Phone: (785) 621-2721

Proposed Plugging Method: PUMP 400# HULLS & 50 SX CMT. GEL SPACER TO 1350'. CMT TO 0'. CHECK BACKSIDE TO 500#.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/15/2010 12:05 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 3498' & 2 SX CMT WITH DUMP BAILER. RAN TBG TO 1378' & CIRCULATED CMT TO SURFACE UP 5 1/2" WITH 120 SX CMT. PULLED TBG OUT & TOPPED OFF 5 1/2" WITH 15 SX CMT. PRESSURED 8 5/8" X 5 1/2" ANNULUS TO 500# WITH 3 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3856	3859	OH	
3751	3753		
3658	3663		

INVOICED
DATE 6/30/10
INV. NO. 2010061319

Remarks: USED COMMON CEMENT BY ALLIED.

Plugged through: TBG

District: 01

Signed Richard W. Lacey

RECEIVED

JUN 22 2010

KCC DODGE CITY

(TECHNICIAN) RECEIVED
KANSAS CORPORATION COMMISSION

JUN 30 2010

CONSERVATION DIVISION
WICHITA, KS

Form CP-33