

\$ 116.55

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-12549-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 19-21S-12W
2310 feet from N Section Line, 2310 feet from E Section Line
Lease Name: E B HALL Well #: 1
County: STAFFORD Total Vertical Depth: 3586 feet

Operator License No.: 33699
Op Name: T-N-T ENGINEERING, INC.
Address: 3711 MAPLEWOOD STE 201
WICHITA FALLS, TX 76308

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	9.625	696		WITH 450 SX CMT
PROD	6.625	3575	0	WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/17/2010 3:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 3350' & 5 SX CMT. PERFORATE @ 720' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE
Date/Time Plugging Completed: 06/17/2010 4:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

**1/5/07: COMPANY RAN 1/2" TBG DOWN 9 5/8" X 6 5/8" ANNULUS TO 520'.
PUMPED 110 SX CMT CIRCULATING CMT TO SURFACE.** SANDED TO 3350' & 5
SX CMT WITH DUMP BAILER. PERFORATED 6 5/8" @ 720'. RAN TBG TO 724'.
PUMPED 130 SX CMT CIRCULATING IT TO SURFACE. PULLED TBG OUT OF HOLE.
DID BULLHEAD SQUEEZE ON 6 5/8" TO 400 PSIG WITH 45 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3575	3586		OHIO
3398	3402		OHIO

INVOICED
DATE 6/30/10
INV. NO. 2010061320

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 30 2010

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

CONSERVATION DIVISION
WICHITA, KS

District: 01

RECEIVED
JUN 22 2010
KCC DODGE CITY

Signed Eric MacLaren
(TECHNICIAN)

Form CR 13