

To: 6. 070800  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 11-8 167-22,876-00-00

SE SE SW, SEC. 15, T 13 S, R 12 W/E

330 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5140

Lease Name Great Plains Well # 1

Operator: Frontier Oil Co.  
Name & Address 125 N. Market 1720  
Wichita, Ks. 67202

County Rnsell 35.00

Well Total Depth 740 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 236

George A. Angle

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_ Drilled to anhydrite and plugged.

Plugging Contractor Red Tiger Drilling Co. License Number \_\_\_\_\_

Address 1720 KS B and T Bldg. Wichita, Ks. 67202

Company to plug at: Hour: PM Day: \_\_\_\_\_ Month: \_\_\_\_\_ Year: 19 \_\_\_\_\_

Plugging proposal received from Ken Lyle

(company name) Red Tiger Drilling Company (phone) \_\_\_\_\_

were: 8 5/8" 236' S.P. cir w/140 sks 60/40 poz 2% gel 3% cal cl. By Allied.

Elv. 1745' Anhy 733'. Lost circulation at 90' cement w/150 sks cement.

Drilled well to anhydrite 740' and plugged. Proposal 180 sks 60/40 poz 4% gel  
3% ca. cl and 8 5/8" plug. Spot with drill stem, circulate, heavy mud between all plugs.

Plugging Proposal Received by Marion Schmidt  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 8:00PM Day: 8 Month: Nov Year: 19 89

ACTUAL PLUGGING REPORT Red Tiger ordered 180 sks 60/40 poz 4% gel and

3% ca cl and 8 5/8" plug. Circulated hole, spotted cement with tubing, heavy mud

between all plugs. 1st plug 50 sks at 710'. 2nd plug 80 sks at 450' w/f.c.

3rd plug 40 sks at 140'. 4th plug 10' sks and plug at 40'. 15 sks in rathole (cir)

Cemented by Allied Cement.

Remarks: (If additional description is necessary, use BACK of this form.)

I (operator) did not observe this plugging.

INVOICED  
DATE 12-7-89

INV. NO. 26674

Signed Marion Schmidt  
(TECHNICIAN)

Marion J. Schmidt

FORM CP-2/3  
Rev. 01-84

RECEIVED  
DEC - 1 1989  
12-01-1989  
CONSERVATION DIVISION  
WICHITA, KANSAS

J.A.S.

11-8