

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

ART NUMBER 15-

SW, Sec. 15, T 13 S, R 12 W/E

990 feet from N/S section line

330 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5131

Lease Name Litch Well # 1

Operator: Thunderbird Drilling Inc.  
Name & Address: Box 97, Ellinwood, Ks  
67526

County Russell

Well Total Depth 3360 feet \$109.20

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8" feet 374'

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Plugging License Number 6050

Address Box 176, Chase, Ks 67524

Company to plug at: Hour: 2:00 PM Day: 5 Month: 10 Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Millard Kelso

(company name) Kelso Casing Plugging (phone) 316-938-2457

were: Order 16 5 sh 5/8" permix - 4 9/16" gel - 3 9/16" lb. U, 15 sh 5/8" hulla, 5 sh hulla, & 8 5/8" plug.

Signed [Signature] (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 5:45 PM Day: 5 Month: Oct. Year: 1983

ACTUAL PLUGGING REPORT 8 5/8" - 374' cas. 4 1/2" set at 3230' w/ 125 sh.

Top perf. at 3114'. Plug bottom w/ 4 sh cement, sand & 4 sh cement to 3050'. Shot pipe 1 time & recovered 2300'. Pumped in 8 5/8" 4 sh hulla, 25 sh cement, 10 sh Gel, 40 sh cement, 5 sh Gel, 1 sh hulla, released plug & followed w/ 100 sh cement w/ 900 pounds.

Remarks: By Boice Cementing Co.

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED  
DATE 10-26-83  
INV. NO. 5876-W

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 14 1983  
10-14-1983  
CONSERVATION DIVISION  
Wichita, Kansas

Signed [Signature] (TECHNICIAN)