

4-16

319P

6 062391

API NUMBER 15-051-02036-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SW 7 11 16  
SEC. \_\_\_\_\_ T \_\_\_\_\_ S, R \_\_\_\_\_ W/E

660 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6718

Lease Name Cora R. Romine Well # 1

Operator: Fell Oil and Gas Co.  
Name & Address: Box 466

County Ellis 107.70

Well Total Depth 3314 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 9 5/8 feet 993

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050

Address Box 347 Chase, Ks. 67524

Company to plug at: Hour: 9:00AM Day: 16 Month: April Year: 19 91

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling Inc. (phone) 316-938-2943

were: Order 300 sks 60/40 poz 8% gel 7 sks hulls.

Plugging Proposal Received by Gilbert G. Scheck  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:00AM Day: 16 Month: April Year: 19 91

ACTUAL PLUGGING REPORT 9 5/8 set at 993 w/cwc sks. 7" set at 3297

w/ 200 sks. Open hole 17'. Plugged bottom w/sand and 7 sks cement

to 3260. Shot pipe two times and recovered 1800.

Pumped in 9 5/8 25 sks cement followed w/7 sks hulls in 300 sks cement

w/400 psi.

STATE CORPORATION COMMISSION  
04-22-91  
APR 22 1991

Remarks: By Allied. Ran line to 1500.  
Additional description is necessary, use BACK of this form.)

INVOICED

I (did / did not) observe this plugging.

Signed Gilbert G. Scheck  
(TECHNICIAN)

DATE: 4-29-91

INV. NO. 31694

Gilbert Scheck

FORM CP-2/3  
Rev. 01-84