

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 051-23,216-0000

SE NE, Sec. 8, T 11 S, R 16 W/E

990 feet from 118 section line

330 feet from 118 section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6725

Lease Name CRAIG Well # 1

Operator: ERIC WADDELL, CO.

County ELLIS

Name & Address NATOMA, KANSAS.  
67651

Well Total Depth 3495 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 170

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor LABANCO DRILLING License Number 458

Address BOX 289, NATOMA, KANSAS. 67651

Company to plug at: Hour: 12:20 PM Day: 21 Month: NOV. Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO JOHN WEIS

(company name) LABANCO DRILLING (phone) 913-885-4676

were: 8 5/8" - 170' ST. CUL. 1/20" ST. COMMON QUICK SET. (BY ALLIED)

ORDER 180' ST. 5/8" PORT MIX 4% GEL-3% CA-CL. AND 8 5/8" PLUG.

SPOT WITH DRILL STEM-WITH HEAVY MUD BETWEEN ALL PLUGS.

1st PLUG @ 3420' EL. 1/20" ST. CMT. - 2nd PLUG @ 1020' EL. 1/20" ST. CMT.

3rd PLUG @ 660' EL. 1/80" ST. CMT. 4th PLUG @ 240' EL. 1/40" ST. CMT.

5th PLUG SOLID BRIDGE HOLES - PLUG @ 40' 1/10" ST. CMT. Signed [Signature]

10th IN RAT HOLE (CIRCULATE) (TECHNICIAN) (DOLIC)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 2:45 PM Day: 21st Month: NOV. Year: 1982

ACTUAL PLUGGING REPORT ORDER 180' ST. 5/8" PORT MIX 4% GEL-3% CA-CL. + 8 5/8" PLUG.

SPOTTED WITH DRILL STEM-WITH HEAVY MUD BETWEEN ALL PLUGS.

1st PLUG @ 3420' EL. 1/20" ST. CMT. -> 2nd PLUG @ 1020' EL. 1/20" ST. CMT.

3rd PLUG @ 660' EL. 1/80" ST. CMT. -> 4th PLUG @ 240' EL. 1/40" ST. CMT.

5th PLUG SOLID BRIDGE HOLES - PLUG @ 40' 1/10" ST. CMT.

10th IN RAT HOLE (CIRCULATE) CEMENTED BY ALLIED OMT.

Remarks: \_\_\_\_\_

RECEIVED  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas  
DEC 6 1982

I hereby certify that the above plugging instructions were given as herein stated and that I (~~did~~ / did not) observe this plugging.

INVOICED  
DATE 12-27-82  
INV. NO. 2014-W

Signed [Signature]  
(TECHNICIAN) (DOLIC)

FORM CP-2/3  
Rev. 9-82