

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-21353-00-00  
Spot: CSWNESW Sec/Twnshp/Rge: 8-11S-16W  
1650 feet from S Section Line, 3630 feet from E Section Line  
Lease/Unit Name: CHESNEY Well Number: 7  
County: ELLIS Total Vertical Depth: 3507 feet

Operator License No.: 6772

Conductor Pipe: Size feet:

Op Name: WEIGEL, V. FRANCIS - FAMILY PARTNE

Surface Casing: Size 8.625 feet: 1048

Address: PO BOX 219  
GORHAM, KS 67640

Production: Size 5.5 feet: 3503

Liner: Size feet:

\$113.98

Well Type: OIL

UIC Docket No: -

Date/Time to Plug: 08/21/2001 2:00 PM

Plug Co. License No.: 31925

Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTYRE

Company: QUALITY WELL SERVICE, INC.

Phone: (620) 727-3410

Proposed Plugging Method: According to KCC Rules & Regulations.  
Ordered 245 sxs 60/40 pozmix - 10% gel - 400# hulls.  
Plug thru casing.

Plugging Proposal Received By: HERB DEINES

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 08/21/2001 4:00 PM

KCC Agent: ROGER MOSES

**Actual Plugging Report:**

8 5/8" casing at 1048'. 5 1/2" casing at 3505'.  
Shot casing off at 2500' - sanded bottom with 5 sxs cement.  
Pulled casing to 1600' - pumped 110 sxs cement with 300# hulls.  
Pulled casing to 1125' - pumped 50 sxs cement with 100# hulls.  
Pulled casing to 600' - pumped 30 sxs cement.  
Pulled casing to 200' and circulated with 10 sxs cement.  
Pulled all casing - cellar full.  
Total of 200 sxs 60/40 pozmix with 10% gel and 400# hulls.  
Dakota 263' to 563'.  
Anhy. 1043' - 1083'.  
Salt 1383' - 1598'.

RECEIVED

SFP 0.4 2001  
09-04-01  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. QUALITY WELL SERVICE - WATER.

Plugged through: CSG

District: 04

Signed

Roger H. Moses

(TECHNICIAN)

INVOICED

DATE 9-4-01

INV. NO. 2002060323

Form CP-2/3

AUG 28 2001

V. FRANCIS WEIGEL  
BOX 244, GORHAM, KS.

#7 CHESNEY

8-11-16W  
SW NE SW

CONTR SHIELDS DRILG. CO. CTY ELLIS

GEOL FRANCIS WHISLER FIELD LIEB

E 1868 KB CM 10/25/77 <sup>CARD</sup> ISSUED 4/13/78 IP P 15 BOPD + 10 BWPD  
SIMP SD 3436-38

API 15-051-21,353

+	+	+	+
+	+	+	+

LOG	TOPS	DEPTH	DATUM
TOP		2786	- 918
HEEB		3022	-1154
TOR		3046	-1178
LKC		3067	-1199
BKC		3316	-1448
CONG		3350	-1482
SP DOI		3408	-1540
SP SD		3436	-1568
ARB		3442	-1574
LTD		3480	-1612
RTD		3507	-1639

8-5/8" 1048, 5 1/2" 3505  
DST (1) 3085-3125/30-60-30-60, 30' TM  
SIP 905-876#, FP 40-40#, 48-48#  
DST (2) 3410-3439/30-60-60-60, 180'  
GIP, 300' MO, SIP 1083-1042# FP  
57-98#, 122-162#  
DST (3) 3443-47/30-30-30-30, 2350'  
SULF WTR, SIP 1107-1107#, FP 325-  
784#, 840-997#  
MICT - PF 3436-38 (SP SD) SWB 1 BOPH  
NAT