

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-25223-00-00  
Spot: SESESW Sec/Twnshp/Rge: 8-11S-16W  
' 330 feet from 'S Section Line, 2780 feet from 'E Section Line  
Lease/Unit Name: ROBERTA Well Number: 1  
County: ELLIS Total Vertical Depth: 3450 feet

Operator License No.: 9860  
Op Name: CASTLE RESOURCES, INC.  
Address: BOX 87  
SCHOENCHEN, KS 67667

Surface Casing Size: 8.625 feet: 209

# 112.13

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/20/2003 3:00 PM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: BILL WYNN Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Order 195 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations Were Not Witnessed  
Date/Time Plugging Completed: 05/20/2003 4:45 PM KCC Agent: HERB DEINES

**Actual Plugging Report:**

1st. Plug at 3390' w/25 sxs. Arbuckle at 3407'.  
2nd. Plug at 1075' w/25 sxs.  
3rd. Plug at 600' w/70 sxs.  
4th. Plug at 260' w/40 sxs.  
5th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.

RECEIVED  
MAY 30 2003  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

INVOICED

5-30-03

2003061590

Form CP-2/3

Bmm

MAY 27 2003