

8 10-12

6 031296

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 167-22,871-00-00
NE, NW NW SEC. 22, T 12S, R 12E
4950 feet from 5 section line
4290 feet from 2 section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5140
Operator: Frontier Oil Co.
Name & Address: 125 N. Market Suite 1720
Wichita, Ks. 67202

Lease Name Johnson
County Russell
Well Total Depth 3300 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 243

RECEIVED
STATE CORPORATION COMMISSION
NOV 20 1989
CONSERVATION DIVISION
Wichita, Kansas
107.25

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Red Tiger Drilling Co. License Number 5302
Address _____

Company to plug at: Hour: PM Day: 12 Month: Oct Year: 19 89

Plugging proposal received from Ken Lyle

(company name) Red Tiger (phone) _____

were: 8 5/8" set at 243' w/c. Circulate hole w/no less than 36 vis mud w/no loss
or gain of fluid, balance plugs w/mud, maintain mud at surface level. Order 180 sks
60/40 poz 6% gel 3% cal cl 8 5/8" wiper plug. Allied Cement Co.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 11:00 P.M. Day: 12 Month: Oct Year: 19 89

ACTUAL PLUGGING REPORT Spot cement plugs w/drill pipe at 725' w/25 sks
660' w/90 sks and hulls.
290' w/40 sks
40' w/10 sks
Circ. 15 sks rat hole w/pipe

Remarks: Anhy 712-747 No arb. Elev. N/A
(If additional description is necessary, use BACK of this form.)

I (did/did not) observe this plugging.

INVOICED

Signed Carl Goodrow
(TECHNICIAN)

DATE 12-4-89
WIK NO. 26552

Paul S

Carl Goodrow
FORM CP-2/3
Rev. 01-84