

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 2/89

**WELL PLUGGING APPLICATION FORM**  
(File One Copy)

API NUMBER 15-051-24,689-0000 (of this well).  
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Eric Waddell Co. OPERATOR'S LICENSE NO. 6725

ADDRESS Box 349 Natoma, KS 67651 PHONE # (913) 885-4497

LEASE (FARM) Craig WELL NO. C-1 WELL LOCATION SW SW SE COUNTY Ellis

SEC. 9 TWP. 11 RGE. 16 (E) or (W) TOTAL DEPTH 3400 PLUG BACK TD         

**Check One:**

OIL WELL          GAS WELL          D & A X SWD or INJ WELL          DOCKET NO.         

SURFACE CASING SIZE 8 5/8 SET AT 207 CEMENTED WITH 130 SACKS

CASING SIZE          SET AT          CEMENTED WITH          SACKS

PERFORATED AT         

CONDITION OF WELL: GOOD X POOR          CASING LEAK          JUNK IN HOLE         

PROPOSED METHOD OF PLUGGING Fill hole 2/ heavy mud; 1st plug at 990' w/25 sx, 2nd plug at 540' w/100 sx, 3rd plug at 250' w/40 sx; 4th plug at 40' w/wiper plug & 10 sx; rathole 15 sx. All cement 50/40 pozmix 6% gel 3% cc.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED?          IS ACO-1 FILED? No  
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 3:00 p.m. 9-17-90

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Harold Maley PHONE # (913) 674-5768

ADDRESS 216 E. McFarland Hill City, KS 67642

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422

ADDRESS 150 N. Main, Suite 801 Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

RECEIVED  
SEP 22 1990  
09-28-90  
CONSERVATION DIVISION  
Wichita, Kansas  
DATE:

SIGNED: Jack K. Wharton  
(Operator or Agent)