

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-21123-00-00
Spot: W2SWSENW Sec/Twnshp/Rge: 29-14S-12W
2970 feet from S Section Line, 3805 feet from E Section Line
Lease Name: EHRlich Well #: 4
County: RUSSELL Total Vertical Depth: 3135 feet

Operator License No.: 33813
Op Name: JASON OIL COMPANY, LLC
Address: 3718- 83RD ST PO BOX 701
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	225	0	w/unknown sxs cmt
PROD	4.5	3050	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/07/2010 9:00 AM
Plug Co. License No.: 33930 Plug Co. Name: SUPER OILWELL SERVICE
Proposal Rcvd. from: TIM BILBERY Company: JASON OIL COMPANY, LLC Phone: (785) 483-4204

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.
P. Plug at 3110'. Steel junk at 2870'.
Perfs: 1300' - 600' - 200'.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/07/2010 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2860' - pumped 25 sxs clean cement - followed with 75 sxs cement with 250# hulls.
Pulled tubing to 1400' - pumped 80 sxs cement with 250# hulls.
Pulled tubing to 400' - pumped 40 sxs cement - cement circulated.
POOH. Hooked to casing and pumped 25 sxs cement.
Max. P.S.I. 200#. S.I.P. 200#.
Hooked to Braden head and pumped 5 sxs cement.
Max. P.S.I. 350#.

Perfs:

INVOICED
DATE 5/19/10
INV. NO. 2010061131

RECEIVED
MAY 17 2010
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3827.

Plugged through: TBG

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

LEO MICHAELIS OIL OPERATOR
 RR#2, RUSSELL, KS.

#4 EHRLICK

29-14-12W
 175'W, SW SE NW

CONTR WOODMAN & IANNITTI DRLG. CTY RUSSELL

GEOL _____ FIELD HALL-GURNEY

K 1671 KB CM 12/12/77 ^{CARD} ISSUED 7/13/78 IP P 8 BOPD + 24 BOPD
 LKC 2818-2903 OA

+	+	+	+
+	+	+	+

API 15-167-21,123

LOG	TOPS	DEPTH	DATUM
1ST TARK	2172	- 501	
2ND TARK	2247	- 576	
TOP	2483	- 812	
TOR	2741	-1070	
KC	2803	-1132	
BKC	3049	-1378	
PENN CONC	3074	-1403	
TD	3135	-1464	

8-5/8" 225, 4 1/2" 3050
 MICT - PF 8/2818-22, 2899-2903, AC
 1500, REC LD, SWB 8 BFPH, 25% OIL, POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS