

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-02143-00-00
Spot: NWSWNE Sec/Twnshp/Rge: 29-14S-12W
3730 feet from S Section Line, 2310 feet from E Section Line
Lease Name: HEIM Well #: 2
County: RUSSELL Total Vertical Depth: 3172 feet

Operator License No.: 31522
Op Name: MICHAELIS, GERALD DBA GERALD M
Address: 979 NW 230TH RD
RUSSELL, KS 67665

MICHAELIS OIL

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	206	0	w/unknown sxs cmt
PROD	4.5	3172	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/10/2010 10:00 AM
Plug Co. License No.: 33385 Plug Co. Name: J & M WELL SERVICING, INC.
Proposal Rcvd. from: GERAL MICHAELIS Company: GERALD MICHAELIS OIL Phone: (620) 935-4230

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 4% gel - 500# hulls.
Perf: 300' - 600' - 1375'.
4 1/2" casing was looking up - Braden head was full of cement.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/10/2010 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2150' - pumped 75 sxs cement with 200# hulls.
Pulled tubing to 1400' - pumped 100 sxs cement with 200# hulls.
Pulled tubing to 400' - pumped 20 sxs cement - cement circulated.
POOH. Hooked to casing - pumped 5 sxs cement.
Max. P.S.I. 300#.
Braden head was full of cement.

Perfs:

INVOICED
DATE 5/19/10
INV. NO. 200061135

RECEIVED
MAY 18 2010
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3830.

Plugged through: TBG

District: 04

Signed

Ray A Dinkel

(TECHNICIAN)

CM

MAY 12 2010

STEARNS DRILLING COMPANY

#2 HEIM

29-14-12W 32
NW SW NE


Contr. _____ RUSSELL _____ County

E. 1660 Comm. 10-17-52 Comp. 1-16-53 IP 50 BOPD

Tops	Depth	Datum
ANH	580	-1080
TARK	2147	-487
KC	2802	-1142
ARB	3160	-1500
TD	3172	-1512

Casing
 8" 206 PERF 3161-65: WTR & SO: PB
 3050: PERF 12/3029-33: 11/
 5" 3172 2994-99, WTR & SSO: PB 2865
 PERF 21/2839-43: ACID 1000
 1.80 & 1 BWPH: PB 2834: PERF
 26/2816-22, WTR: PB 2180:
 PERF 32/2170-74: SANDFRAC,
 2 80 & 1 1/2 BW

HALL-GURNEY POOL



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS