

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-03178-00-00
Spot: SENWSW Sec/Twnshp/Rge: 21-10S-23W
1650 feet from S Section Line, 4290 feet from E Section Line
Lease Name: DIEBOLT LKC UNIT Well #: 7-2
County: GRAHAM Total Vertical Depth: 3874 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	237	0	150 SX
PROD	5.5	3882	0	175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/10/2010 10:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 700# hulls.
Shoot perfs at 225' - 1050' - 1975' - 2500'.
CIBP at 3400'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/10/2010 1:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Shot perfs at 225' - 1050' - 1975' - 2500'.
Ran tubing to 3328' - pumped 125 sxs cement with 200# hulls.
Pulled tubing to 2076' - pumped 100 sxs cement with 200# hulls.
Pulled tubing to 1086' - pumped 40 sxs cement - good circulation of cement.
Pulled tubing out - tied onto casing - squeezed with 35 sxs cement - circulated out 8 5/8".
Pumped 100 sxs cement down 5 1/2".
Max. P.S.I. 200#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3846	3856		LKC 'K'
3826	3835		LKC 'J'
3809	3819		LKC 'I'
3787	3795		LKC 'H'
3746	3752		LKC 'G'
3730	3735		LKC 'F'
3717	3725		LKC 'E'

INVOICED
DATE 5/19/10
W. NO. 2010061136

RECEIVED
MAY 17 2010


Remarks: LEASE ALSO KNOWN AS N. BROWN #2. ALLIED CEMENTING COMPANY.

KCC WICHITA

Plugged through: TBG

District: 04

Signed _____



(TECHNICIAN)

CM

MAY 10 2010

MID CONTINENT PETROLEUM #2 N BROWN 21-10-23W
 SE NW SW


Contr. GABBERT & JONES GRAHAM County

E 2391 RB Comm. Comp. 7-9-54 IP 3000 BOPD
 BOMB POT

Tops	Depth	Datum
HEEB	3606	-1215
TOR	3622	-1231
LANS	3638	-1247
TD	3888	-1497

Casing
 8" 237
 5" 3887
 PERF 3809-18: 3826-35: ACID
 3000: FLO 30 BOPH

HAPPY POOL



INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS