

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-03179-00-00
Spot: SESWSW Sec/Twnshp/Rge: 21-10S-23W
330 feet from S Section Line, 4290 feet from E Section Line
Lease Name: DIEBOLT LKC UNIT Well #: 7-3
County: GRAHAM Total Vertical Depth: 3891 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	242	0	150 SX
PROD	5.5	3890	0	175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/14/2010 10:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 700# hulls.
Shoot perms: 225' - 1050' - 1975' -2500'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/14/2010 1:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3568' - pumped 125 sxs cement with 350# hulls.
Pulled tubing to 2702' - pumped 125 sxs cement with 200# hulls.
Pulled tubing to 806' - pumped 100 sxs cement - good circulation of cement.
Pulled tubing out - tied onto 5 1/2" - pumped 30 sxs cement - circulated out backside - good cement.
Shut off backside - squeezed 5 1/2" with 30 sxs cement.
Max. P.S.I. 200#. S.I.P. 50#.

Perfs:

Top	Bot	Thru	Comments
3860	3865		LKC 'K'
3833	3843		KJC 'J'
3818	3826		LKC 'I'
3750	3758		LKC 'G'
3728	3734		LKC 'F'

3654 3658 LKC 'A'
INVOICED
DATE: 5/19/10
INVOICE NO: 2010061136
RECEIVED
MAY 18 2010
KCC WICHITA

Remarks: LEASE ORIGINALLY KNOWN AS N.BROWN #3. ALLIED CEMENTING COMPANY-TICKET #41369.

Plugged through: TBG

District: 04

Signed 
(TECHNICIAN)

CM

MAY 17 2010

MID CONTINENT PETROLEUM #3 N BROWN

21-10-23W
SE SW SW

Contr. GABBERT-JONES

GRAHAM County

E 2393 RB Comm.

Comp. 7-9-54

IP 2023 BOPD
BOMB POT

Tops	Depth	Datum
HEEB	3612	-1219
TOR	3632	-1239
LANS	3645	-1252
TD	3891	-1498

Casing
8" 250
5" 3890
PERF 3860-68: 3840-43: 3818-
26; ACID 3000; SWB 25 BOPH

HARRY SE POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS