

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20478-00-00
Spot: SWSESW Sec/Twnshp/Rge: 20-8S-17W
330 feet from S Section Line, 3630 feet from E Section Line
Lease Name: RUSS Well #: 1
County: ROOKS Total Vertical Depth: 3352 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	200	0	130 SX
PROD	5.5	3328	0	100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/29/2010 10:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: THOMAS ATKINS Company: RITCHIE EXPLORATION, INC. Phone: (785) 216-0155

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 600# hulls.
Tubing stacked out at approximately 2200'.
Perfed at 1250' and 180'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/29/2010 1:15 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2200' - pumped 80 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 1400' - pumped 100 sxs 60/40 pozmix - 4% gel with 100# hulls to circulate to surface.
Pulled all tubing. Hooked to 8 5/8" x 5 1/2" annulus - pumped 65 sxs 60/40 pozmix - 4% gel to fill annulus and 5 1/2" casing.
S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3328	3352		ARBUCKLE
3098	3102		LKC

VOICED
DATE: 5/19/10
NV NO. 201006138

RECEIVED
MAY 17 2010

Remarks: ALLIED CEMENTING COMPANY-TICKET #41359.

Plugged through: TBG

KCC WICHITA

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

MAY 05 2010

A. SCOTT RITCHIE & MADEIRA OIL #1 RUSS

20-8-17W
SW SE SW

412 UNION CENTER, WICHITA, KS.

CONTR C-G DRILLING

CTY ROOKS

GEOL

FIELD DOPITA

E 1904 KB CM 11/29/72 ^{WARD} ISSUED 5/10/73 IP P 40 BOPD + WTR

ARB 3328-3352

API 15-163-20,478

LOG	TOPS	DEPTH	DATUM
ANHY		1239	+ 665
B ANHY		1276	+ 628
TOP		2806	- 902
HEEB		3018	-1114
TOR		3038	-1134
LKC		3059	-1155
BKC		3285	-1381
ARB		3325	-1421
ARB POR		3329	-1425
LTD		3333	-1429
DDTD		3352	-1448

8 5/8" 200/130SX; 5 1/2" 3328/100SX
DST(1) 2984-3050/90", 1060' MSW W/SC OIL
BHP 1211-1121#/45", FP 76-469#
DST(2) 3100-3160/1 1/2", 60' GIP, 90' HO &
GCM, 120' MGO, 200' GSY OIL, BHP 879-
858#/45", FP 66-153#, FP 186-229#
DST(3) 3160-3205/90", 250' MW(SSFO) BHP
404-404#/45", FP 44-109# & 120-164#
DST(4) 3204-3230/1', 60' M, BHP 328-
251#/30", FP 44-55#
MICT, COTD-DD 3352, A500, SWB 2BFPH
50% OIL/4HRS, RE-AC 500 28% + 1000 15%
REC LD SWB 12BFPH 50%/1HR, SWB 6 1/2
BFPH 50% OIL/3HRS, 300' OB

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS