

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24478-00-01
Spot: NWSWNW Sec/Twnshp/Rge: 19-20S-15W
3641 feet from S Section Line, 5102 feet from E Section Line
Lease Name: IANNITTI Well #: 6
County: BARTON Total Vertical Depth: 4020 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 1327 NOOSE RD PO BOX 458
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1116	0	400 SX
PROD	5.5	4019	1679	150 SX

Well Type: SWD UIC Docket No: D26499.0 Date/Time to Plug: 04/29/2010 10:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: TIM DICKSON Company: TENGASCO, INC. Phone: (620) 793-5838

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/29/2010 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perfs - topped with 5 sxs cement.
Shot off casing at 1679' - pulled to 1640' - pumped 125 sxs cement with 200# hulls.
Pulled to 730' - pumped 50 sxs cement with 100# hulls.
Pulled to 150' - pumped 45 sxs cement - circulated cement to surface.
Pulled casing - hole stayed full.

Perfs:

Top	Bot	Thru	Comments
3950	3970		

INVOICED
DATE 5/19/10
INV. NO. 2010061140
RECEIVED
MAY 17 2010

Remarks: ALLIED CEMENTING COMPANY-TICKET #36414.

Plugged through: CSG

KCC WICHITA

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

MAY 03 2010

STATE: KANSAS COUNTY: BARTON
FIELD: PAWNEE ROCK FLD(ARBUCKLE)
OPER: IANNITTI OIL
WELL: 6 IANNITTI
API: 15-009-24478
SPUD: 09/20/91
DTD: 4020 LTD: 4015 FTD: ARBUCKLE

WELL CLASS: D
STATUS: D&A-O
COMP: 01/15/92

19-20S-15W
NW SW NW
3630 FSL 4950 FEL SEC
ELEV: 2106 KB
2101 GR

PBTD:

LOC: 1 3/4 MI NW PAWNEE ROCK, KS

IP: COMP 1/15/92, D&A (TO CONVERT TO SWDW)
NO CORES, FOUR DSTS

LOG TOPS:

ANHYDRITE	1110 996	BROWN LIME	3505 -1399
BSE ANHYDRITE	1134 972	LANSING-KANSAS CITY	3516 -1410
HEEBNER	3418 -1312	LANSING-KANSAS CITY GY	3586 -1480
TORONTO	3435 -1329	BSE KANSAS CITY	3746 -1640
DOUGLAS	3446 -1340	ARBUCKLE	3805 -1699
TD	4020 -1914		

LOG TYPES: CDL, CNL, DNL;

CSGS: 8 5/8 @ 1116 W/400 SX, 5 1/2 @ 4019 W/150 SX; TBG: 2 3/8 @ 3910, PSA 3910;
DRLG COMP 09/27/91 RIG REL 09/28/91

DSTS: DST # 1 (ARBUCKLE) 3807-3814, (MISRUN) DST # 2 (KANSAS CITY)

(OVER)

COPYRIGHT 1992 PETROLEUM INFORMATION CORPORATION

DATE 02/14/92 CARD #00036-KS