

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-20528-00-00  
Spot: NWNWSW Sec/Twnshp/Rge: 24-14S-11W  
2310 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: SEBESTA Well #: 11  
County: RUSSELL Total Vertical Depth: 2250 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 S MAIN STE 200  
WICHITA, KS 67202

| String | Size  | Depth (ft) | Pulled (ft) | Comments   |
|--------|-------|------------|-------------|------------|
| SURF   | 8.625 | 213        | 0           | 160 SX CMT |
| PROD   | 5.5   | 2249       | 0           | 75 SX CMT  |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/04/2010 10:00 AM  
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.  
Proposal Rcvd. from: KEN Company: TRANS PACIFIC OIL CORPORATIO Phone: (785) 483-1821

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 400# hulls - 3 sxs gel.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/04/2010 2:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing 2200' - pumped 3 sxs gel - followed with 50 sxs cement with 150# hulls.  
Pulled tubing to 1400' - pumped 100 sxs cement with 250# hulls.  
Pulled tubing to 400' - pumped 40 sxs cement. - cement circulated.  
POOH. Hooked up to casing and pumped 5 sxs cement.  
Max. P.S.I. 300#. S.I.P. 275#.  
Hooked to Braden head and pumped 5 sxs cement.  
Max. P.S.I. 300#.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 2073 | 2080 |      |          |

INVOICED  
DATE: 5/19/10  
INV. NO. 2010061141

RECEIVED  
MAY 17 2010

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3870.

Plugged through: TBG

KCC WICHITA

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

