

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-20535-00-00  
Spot: SESWNE Sec/Twnshp/Rge: 23-14S-11W  
2970 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: SMALL A Well #: 1  
County: RUSSELL Total Vertical Depth: 2113 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 S MAIN STE 200  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	216	0	160 SX
PROD	5.5	2113	0	85 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/05/2010 1:00 PM  
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.  
Proposal Rcvd. from: KEN Company: TRANS PACIFIC OIL CORPORATIO Phone: (785) 483-1821

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.  
Perfs: 1400' - 515' - 310'.

Plugging Proposal Received By: RAY DINKEL WitnessType: NONE  
Date/Time Plugging Completed: 05/05/2010 3:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing 2075' - pumped 65 sxs cement with 200# hulls.  
Pulled tubing to 1430' - pumped 100 sxs cement with 300# hulls.  
Pulled tubing 400' - pumped 40 sxs cement - cement circulated.  
POOH. Hooked to casing - pumped 5 sxs cement.  
Max. P.S.I. 300#. S.I.P. 300#.  
Hooked to Braden head - pumped 5 sxs cement.  
Max. P.S.I. 300#.

Perfs:

INVOICED  
5/19/10  
2010061141

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3871.

Plugged through: TBG

RECEIVED  
MAY 17 2010  
KCC WICHITA

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

Form CP-2/3

MAY 07 2010

WILL P. ASH #1 SMALL "A" 23-14-11W  
 WICHITA, KANSAS SE SW NE  
 CONTR SAGE DRILLING CTY RUSSELL

GEOL \_\_\_\_\_ FIELD WILSON CREEK

E 1681 KB CM4/22/72 CARD ISSUED 6/8/72 IP P 55 BOPD + 14% WTR  
 TARK 2091-2104  
 GR 37

+	+	+
+	+	+
+	+	+

API 15-167-20,535

SMP	TOPS	DEPTH	DATUM
ANHY		499	+1182
B ANHY		528	+1153
BROWNVILLE		2047	- 366
GR HAV		2088	- 407
DOVER		2111	- 430
TARK 1M		2167	- 486
WILLARD		2191	- 510
RTD		2214	- 533

8 5/8" 216/160sx; 5 1/2" 2113/85.  
 DST(1) 2091-2112/90-90-90-90, GTS/50",  
 TSTM, 750' CGO, 60' HO&GCM, N/W, BHP  
 628-620#, FP 41-167# & 209-284#  
 DST(2) 2177-2214/60-60-60-60, 360' GIP,  
 90' O&GCMW, BHP 736-699#, FP 38-47#  
 & 57-66#  
 MICT, PF 2091-2104, A250 & FRAC 15,000#  
 SD & 820 BLB, POP

NO LOG

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS