

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-19558-00-00  
Spot: SENWSE Sec/Twnshp/Rge: 23-28S-7E  
1573 feet from S Section Line, 4707 feet from E Section Line  
Lease Name: BREWER Well #: 5  
County: BUTLER Total Vertical Depth: 2747 feet

\$89.28

Operator License No.: 5387  
Op Name: THE BUCKEYE CORPORATION DBA A  
Address: PO BOX 1020  
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	58		35 SX
PROD	5.5	2724		35 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/08/2010 8:00 AM  
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.  
Proposal Revd. from: STEVEN W. KILE Company: AZTEC OIL CO. Phone: (316) 321-3800

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 04/09/2010 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2684', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL 3% CC. AND DISPLACED IN CASING. WAITED 2 HOURS. TAGGED CEMENT @ 2436'. PARTED 5-1/2" CASING @ 251', LAYED CASING DOWN. RIH W/TBG 2 254', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, & MIXED & PUMPED 133 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. P.A. COMPLETE 5:00 PM, 4-9-2010. CEMENT TICKET # 23368.

Perfs:

Top	Bot	Thru	Comments
2724	2747	OH	OH

INVOICED

DATE 5/20/10  
INV. NO. 2010061143


RECEIVED  
MAY 19 2010  
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

JK