

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-20628-00-01  
Spot: NWNW Sec/Twnshp/Rge: 26-24S-15W  
660 feet from N Section Line, 660 feet from W Section Line  
Lease Name: PILAND OWWO Well #: 1  
County: STAFFORD Total Vertical Depth: 4420 feet

B 143.65

Operator License No.: 31021  
Op Name: CASTELLI EXPLORATION, INC.  
Address: 6908 W 112TH  
OKLAHOMA CITY, OK 73162

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	266		WITH 225 SX CMT
PROD	4.5	4406	2050	WITH 200 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/03/2010 10:30 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-5514

Proposed Plugging Method: PUMP 40 SX CMT TO 4100'. PLUG AT 990' WITH 15 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: \_\_\_\_\_ KCC Agent: RICHARD LACEY

Actual Plugging Report:

PUMPED 100# HULLS & 40 SX CMT. TAGGED CMT @ 4020'. 1ST PLUG AT 990' WITH 100# HULLS- 15 SX GEL - 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4141	4145		
4118	4134		

INVOICE  
DATE 5/20/10  
INV. NO. 2010061144

RECEIVED

MAY 19 2010

KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: CSG

District: 01

Signed Richard W. Lacey  
(TECHNICIAN)

RECEIVED

MAY - 7 2010

KCC DODGE CITY

Form CP-28