

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-20949-00-00  
Spot: W2SESENW Sec/Twnshp/Rge: 27-16S-10W <sup>8</sup> 107.41  
2970 feet from S Section Line, 3045 feet from E Section Line  
Lease Name: STOLTENBERG A Well #: 3  
County: ELLSWORTH Total Vertical Depth: 3305 feet

Operator License No.: 6901  
Op Name: D S & W WELL SERVICING, INC.  
Address: 1822 24TH STREET  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	296		185 SXS CMT
PROD	5.5	3304	1576	150 SXS CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/05/2010 9:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: TIM DICKSON Company: D S & W WELL SERVICING INC Phone: (620) 786-4258

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: SHANE JONES Witness Type: NONE  
Date/Time Plugging Completed: 05/05/2010 10:45 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND PERFS TO 2940' AND CAP WITH 5 SX'S CEMENT. CUT CASING AT 1576' AND PULL TO 1350' AND PUMP 35 SX'S COMMON CEMENT WITH 50 #'S COTTON HULLS. PULL CASING TO 1000' AND PUMP 35 SX'S COMMON CEMENT WITH 50 #'W COTTON HULLS. PULL CASING TO 350' AND CIRCULATE 60-40 POZ, 4% GEL TO SURFACE. PULL CASING OUT AND TOP OFF. USED 200 SX'S CEMENT.

Perfs:

Top	Bot	Thru	Comments
3270	3271	CSG	
3178	3184	CSG	
2992	2998	CSG	

INVOICED  
DATE: 5/20/10  
INV. NO. 201006/146

RECEIVED  
MAY 19 2010

Remarks: COPELAND TICKET #C-36517.

Plugged through: CSG

KCC WICHITA

District: 02

Signed [Signature] DISTRICT SUPERVISOR  
(TECHNICIAN)