

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-047-21519-00-00  
Spot: SESWSW .Sec/Twnshp/Rge: 4-26S-19W  
330 feet from S Section Line, 990 feet from W Section Line  
Lease Name: FOX GAS UNIT B Well #: 2-4  
County: EDWARDS Total Vertical Depth: 4820 feet

\$156.65

Operator License No.: 5003  
Op Name: MCCOY PETROLEUM CORPORATION  
Address: 8080 E CENTRAL STE 300  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4690		
SURF	8.625	337		WITH 275 SX CMT
PROD	4.5	4822	2640	WITH 200 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/12/2010 2:30 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 150# HULLS & 25 SX CMT TO BOTTOM. PLUG AT 1300' WITH 15 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: PARTIAL  
Date/Time Plugging Completed: 05/12/2010 3:40 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PUMPED 150# HULLS & 25 SX CMT TO BOTTOM. TAGGED TOP OF CMT @ 3975'.  
1ST PLUG AT 1300' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 360' WITH 50 SX  
CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4766	4772		
4214	4218		
4211	4213		

NOV 10 10 10  
DATE: 5/20/10  
INV NO. 2010061157

RECEIVED  
MAY 19 2010

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

KCC WICHITA

Plugged through: CSG

District: 01

Signed Richard W. Lacey  
(TECHNICIAN)

RECEIVED

MAY 14 2010

KCC DODGE CITY

Form SP-273