

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-22225-00-00
Spot: W2 Sec/Twnshp/Rge: 9-20S-28W
2590 feet from S Section Line, 1220 feet from W Section Line
Lease Name: MOOMAW 'A' UNIT Well #: 1-9
County: LANE Total Vertical Depth: 4685 feet

\$ 152.26

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 8080 E CENTRAL STE 300
WICHITA, KS 67206

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-----------------|
| SURF | 8.625 | 214 | | WITH 150 SX CMT |

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/08/2010 6:15 AM
Plug Co. License No.: 5142 Plug Co. Name: STERLING DRILLING COMPANY
Proposal Rcvd. from: LARRY HUNT Company: STERLING DRILLING COMPANY Phone: (620) 672-9508

Proposed Plugging Method: 1ST PLUG AT 2080' WITH 50 SX CMT. 2ND PLUG AT 1300' WITH 80 SX CMT. 3RD PLUG AT 650' WITH 50 SX CMT. 4TH PLUG AT 240' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: NONE
Date/Time Plugging Completed: 05/08/2010 8:15 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

1ST PLUG AT 2080' WITH 50 SX CMT. 2ND PLUG AT 1300' WITH 80 SX CMT. 3RD PLUG AT 650' WITH 50 SX CMT. 4TH PLUG AT 240' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

INVOICED
DATE: 5/20/10
INV. NO. 2010061151

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY QULAITY OIL WELL CEMENTING.

Plugged through: DP

RECEIVED
MAY 19 2010
KCC WICHITA

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
MAY 11 2010

KCC DODGE CITY

Form CP-273