

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-21526-00-01 # 154.86
Spot: E2NWNW Sec/Twnshp/Rge: 20-26S-18W
660 feet from N Section Line, 990 feet from W Section Line
Lease Name: STURGEON A Well #: 1-20
County: EDWARDS Total Vertical Depth: 4765 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 8080 E CENTRAL STE 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4500		
SURF	8.625	356		WITH 275 SX CMT
PROD	4.5	4763	2650	WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/11/2010 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 150# HULLS & 25 SX CMT @ 3888'. PLUG AT 1280' WITH 50 SX CMT. PLUG AT 390' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: JACK MACLASKEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/11/2010 3:46 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PUMPED 150# HULLS & 25 SX CMT TO BOTTOM @ 2000 PSIG. TAGGED TOP OF CMT AT 3780'. 1ST PLUG AT 1280' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 390' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 25 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3888	3892		

INVOICED
DATE: 5/20/10
INV. NO. 2010061151

RECEIVED
MAY 19 2010

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: CSG

KCC WICHITA

District: 01

Signed Richard W. Lacey

(TECHNICIAN)

RECEIVED
MAY 14 2010
KCC DODGE CITY

Form CC-203