

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-21906-00-00  
Spot: NENESE Sec/Twnshp/Rge: 27-19S-9W \$ 104.78  
2313 feet from S Section Line, 462 feet from E Section Line  
Lease Name: HAXTON Well #: 1  
County: RICE Total Vertical Depth: 3224 feet

Operator License No.: 9292  
Op Name: SCHECK, TIMOTHY DBA SCHECK OIL  
Address: 211 S FRONT ST  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	211		135 sx's
PROD	4.5	3214	2000	150 sx's

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/20/2010 3:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL  
Date/Time Plugging Completed: 04/20/2010 4:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND OPEN HOLE TO 3050' AND CAP WITH 4 SX'S CEMENT. CUT CASING @ 2000' AND PULL TO 1150' AND PUMP 35 SX'S COMMON CEMENT WITH 100#'S COTTON HULLS. PULL CASING TO 750' AND PUMP 35 SXS'S COMMON CEMENT WITH 100#'S COTTON HULLS. PULL CASING TO 261' AND CIRCULATE 60-40 POZ, 4% GEL TO SURFACE. PULL CASING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3214	3224	OH	

INVOICED  
DATE 5/20/10  
INV NO. 2010061154

RECEIVED  
MAY 19 2010

Remarks: COPELAND CEMENT TICKET #C-36505

Plugged through: CSG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

KCC WICHITA