

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-00443-00-00
Spot: NWNENW Sec/Twnshp/Rge: 30-23S-15W
330 feet from N Section Line, 1650 feet from W Section Line
Lease Name: R J BENSON Well #: 1
County: PAWNEE Total Vertical Depth: 4165 feet

5
135.36

Operator License No.: 33699
Op Name: T-N-T ENGINEERING, INC.
Address: 3711 MAPLEWOOD STE 201
WICHITA FALLS, TX 76308

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4005		
CIBP		4077		
SURF	13.38	383		WITH 300 SX CMT
PROD	5.5	4165	0	WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/04/2010 11:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 3640' & 5 SX CMT. PERFORATE 5 1/2" @ 1000'. RUN TBG TO 1500' PUMP 10 SX GEL - 25 SX CMT. PULL TBG TO 1000' & CIRCULATE 5 1/2" FULL OF CMT. PULL TBG & TOP OFF 5 1/2". PRESSURE TEST 13 3/8" X 5 1/2" ANNULUS WITH CMT TO 500 PSIG.

INVOICED
5/20/10

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%) NO.
Date/Time Plugging Completed: 05/04/2010 12:30 PM KCC Agent: RICHARD LACEY

2010061156

Actual Plugging Report:

SQUEEZED @ 3690-3696, 3622-28, 2618-2628, 3012-3041' WITH 100 SX CMT, 3368-3415 W/150 SX CMT, 1475-1506 WITH 150 SX CMT, 444-450 WITH 375 SX CMT.
SANDED BOTTOM TO 3591' & 5 SX CMT WITH DUMP BAILER. PERFORATED 5 1/2" CASING @ 1000'. RAN TBG TO 1500'. PUMPED 10 SX GEL & 25 SX CMT. PULLED TBG TO 1000' & CIRCULATED CMT TO SURFACE WITH 105 SX CMT. PULLED TBG OUT OF HOLE & TOPPED OFF 5 1/2" CASING WITH 30 SX CMT. PRESSURED 13 3/8" X 5 1/2" TO 500 PSIG WITH 5 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4140	4150		ARB
4100	4140		ARB
4058	4062		ARB
3853	3869		L-KC
3821	3831		L-KC
3798	3807		L-KC
3791	3795		L-KC
3763	3764		L-KC
3748	3760		L-KC
3703	3726		L-KC
3690	3696		SQZD. W/ CMT.
2618	2628		SQZD. W/ CMT.

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: TBG

RECEIVED
MAY 19 2010

KCC WICHITA

District: 01

RECEIVED
MAY - 7 2010
KCC DODGE CITY

Signed Richard W. Lacey
(TECHNICIAN)

Form CR-23