

\$ 119.76

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-20805-00-00
Spot: NESWNE Sec/Twnshp/Rge: 21-21S-12W
3655 feet from S Section Line, 1694 feet from E Section Line
Lease Name: REISER Well #: 2
County: STAFFORD Total Vertical Depth: 3685 feet

Operator License No.: 5141
Op Name: ZENITH DRILLING CORPORATION
Address: PO BOX 780428
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	265		
PROD	5.5	3685	0	WITH 80 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/06/2010 1:00 PM
Plug Co. License No.: 33645 Plug Co. Name: H2 PLAINS, LLC
Proposal Rcvd. from: ALLEN WALKER Company: ZENITH DRILLING Phone: (316) 684-9777

Proposed Plugging Method: RUN TBG TO 3500' & PUMP 100# HULLS & 50 SX CMT. PERFORATE 5 1/2" @ 690'. RUN TBG TO 700' & CIRCULATE CMT TO SURFACE UP 5 1/2" & 8 5/8" IF POSSIBLE. IF NO RETURNS PRESSURE 8 5/8" X 5 1/2" ANNULUS TO 500 PSIG WITH 100 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/06/2010 3:25 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

****CASING LEAK @ 500'. COMPANY ATTEMPTED TO PULL 5 1/2" BUT IT APPREARED THAT CASING WAS SQUEEZED IN.** RAN TBG TO 3444' & PUMPED 100# HULLS- 50 SX CMT DISPLACED TO BOTTOM. PERFORATED 5 1/2" @ 690'. PULLED TBG TO 710' PUMPED 130 SX CMT CIRCULATING CMT TO SURFACE UP 5 1/2". HAD GOOD RETURNS UP 8 5/8" X 5 1/2" ANNULUS BUT NO CMT. PULLED TBG OUT OF HOLE. PUMPED DOWN 5 1/2" WITH 45 SX CMT CIRCULATING CMT TO SURFACE UP 8 5/8" X 5 1/2" ANNULUS.**

Perfs:

Top	Bot	Thru	Comments
3655	3659		
3635	3644		
3594	3598		
3570	3576		

INVOICED
DATE: 5/20/10
INV NO: 2010061157

RECEIVED
MAY 19 2010

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

KCC WICHITA

Plugged through: TBG

District: 01

Signed Richard W. Lacey

(TECHNICIAN)

RECEIVED

MAY 14 2010

KCC DODGE CITY

Form 0527