

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev.03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

Drilled

API # 6-30-1940 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Lario Oil & Gas Company KCC LICENSE # 5214 (owner/company name) (operator's)

ADDRESS 301 S. Market CITY Wichita

STATE KS ZIP CODE 67202 CONTACT PHONE # (316) 265-5611

LEASE Romine WELL# 6 SEC. 18 T. 11 R. 16 (XXX/ West)

W/2 - NW - SW - SPOT LOCATION/QQQQ COUNTY Ellis

1980 FEET (in exact footage) FROM S/X (circle one) LINE OF SECTION (NOT Lease Line)

4950 FEET (in exact footage) FROM E/X (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE None SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8-5/8" SET AT 1056' CEMENTED WITH 350 SACKS

PRODUCTION CASING SIZE 5-1/2" SET AT 3347' CEMENTED WITH 100 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Open hole from 3347' to 3364'

ELEVATION 1833'DF (G.L./K.B.) T.D. 3364' PBTD 3364' ANHYDRITE DEPTH 1000' (Stone Corral Formation)

Casing leak cemented at 1230' with 300 sxs circ. to surface thru Bradenhead.
CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING 30 sxs cement plug from 3150'-3250' with open ended tubing.

30 sxs cement plug from 1006' to 1106'. 10 sxs cement plug from 0' to 30'. Weld metal plate on top. Casing will not be pulled.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? YES

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101, et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Tim Gillogly PHONE# (316) 625-5023

ADDRESS P. O. Box 784 City/State Hays, KS 67601

PLUGGING CONTRACTOR Allied Cementing KCC LICENSE # NA

ADDRESS Box 628, Great Bend, KS 67530 (company name) (contractor's)
PHONE # (316) 793-5861

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) As soon as plugging is approved

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 4-16-97 AUTHORIZED OPERATOR/AGENT: Dava (signature)

Note: The surface casing is set deep enough to protect the Dakota Sand

STATE CORPORATION COMMISSION
APR 18 1997
CONSERVATION DIVISION
Wichita, Kansas

4



15-051-03288-0000

Kansas Corporation Commission

Bill Graves, Governor Timothy E. McKee, Chair Susan M. Seltsam, Commissioner John Wine, Commissioner
Judith McConnell, Executive Director David J. Heinemann, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

April 21, 1997

Lario Oil & Gas Company
301 S Market
Wichita KS 67202

Romine #6
API 15-N/A
1980 FSL 4950 FEL
Sec. 18-11S-16W
Ellis County

Dear Tim Gillogly,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
Production Supervisor

District: #4
2301 E 13th
Hays KS 67601
(913) 628-1200