

KANSAS

Form CP-3
Rev. 6-26-62



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT
RECEIVED
STATE CORPORATION COMMISSION
AUG 26 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Prospect Oil, Inc. & Shields

Complete Address: 811 Union Center Wichita, Kansas

Lease Name Craig Well No. 1

Location NE NW SW Sec. 9 Twp. 11 Rge. 16 (E) (W) X

County Ellis Total Depth 3465

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Shields Drlg.

Address: Russell, Ks. License No. _____

Operation Completed: Hour 4 P Day 25 Month 8 Year 1968

The Above well was plugged as follows:

RTD 3465' 8 5/8 csg set at 250' cwc. Cem. Mat. 100 sc 50-50 poz cem. W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 540' and displaced 70 sc cem.
thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/26/68
INV. NO. 8350-U

Signed: Leo J. Massey
Well Plugging Supervisor