

15-057-02041-0000

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 21 1959
12-21-59
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Ellis

Location: SE NW SW Sec. 8 Twp. 11 Rge. 16 (E) (W)

Name of Field: _____ Total Depth: 3416

I have this date completed supervision of plugging of:

Lease Name: Lieb Well No. 4

Operator's Full Name: Frontier Oil Co

Complete Address: 580 4th Natl Bk Bldg Wichita, Kans

Plugging Contractor: Barnes & Sons

Address: Russell, Kans License No. 9

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 5PM Day 15 Month 12 Year 59

The above well was plugged as follows:

8 5/8" 1024' circulated with cement, 5 1/2" 3412' with 150 sax cement.
Filled with sand to 3400', set 4 sax cement with dump bailer, pulled
2705' 5 1/2" to 480', circulated hole with heavy mud through 5 1/2" at 480'
(Gel mud), displaced 20 sax cement through 5 1/2" at 480', heavy mud to
150', displaced 20 sax cement through 5 1/2" at 150', heavy mud to 35', set
bridge and 10 sax cement to bottom cellar.
Mudding and cementing by Sun Cementing Co.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 1/14/60
INV. NO. 550-w