

15-051-20903-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 22 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name F & M Oil Co., Inc.
Complete Address 603 Union Center Wichita, Kansas
Lease Name Craig Well No. 1
Location SE SE SW Sec. 9 Twp. 11 Rge. (E) (W) 16
County Ellis Total Depth 3430'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Rains & Williamson Oil
Address Wichita, Kansas License No.
Operation Completed: Hour 4:30 A Day 21 Month 6 Year 1973

The above well was plugged as follows:

RTD 3430' 8 5/8 csg set at 222' cwc 140 sk. Cmt. Mat. 50-50 poz W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 480' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/4 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Messing
Well Plugging Supervisor

DATE 6/22/73
INV. NO. 7543-W