

15-051-02040-0000

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

R

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Ellis

Location: NW SE SW Sec. 8 Twp. 11 Rge. 16 (E) (W)

Name of Field: _____ Total Depth: 3412

I have this date completed supervision of plugging of:

Lease Name: Lieb Well No. 3

Operator's Full Name: Frontier Oil Co

Complete Address: 580 4th Natl Bk Bldg Wichita, Kans

Plugging Contractor: Barnes & Sons & Sun Cementing Co

Address: Russell, Kans License No. 9

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 10 AM Day 30 Month 3 Year 59

The above well was plugged as follows:

8 5/8" at 1045' circulated with cement - 5 1/2" 3412' with 125 sax cement, perforated 3395'.

Filled with sand to 3385', set 4 sax cement with dump bailer, pulled 2700' 5 1/2" to 500', circulated hole with heavy mud through 5 1/2" (23 sax Gel) displaced 25 sax cement through 5 1/2" at 500', heavy mud to 160', displaced 20 sax cement through 5 1/2", heavy mud to 35', set bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Sun Cementing Co.

Signed: *Edwin Petty*
Conservation Division Agent

Reviewed: *J. Lewis Brock*
Field Supervisor

Remarks:

PLUGGING
FILE SEC. 8 T. 11 R. 16W
BOOK PAGE 28 LINE 30

RECEIVED
STATE CORPORATION COMMISSION
APR 16 1959
04-16-59
CONSERVATION DIVISION
Wichita, Kansas