


15-051-20255-0000

Form CP-3  
Rev. 6-26-62

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 23 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Murfin Drilling Company  
Complete Address: 817 Union Center Bldg., Wichita, Kansas  
Lease Name Chesney "B" Well No. 1  
Location NW SW NW Sec. 8 Twp. 11 Rge. 16 (E) (W) X  
County Ellis Total Depth 3431  
Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X  
Other well as hereafter indicated:       
Plugging Contractor: Co. Tools  
Address:      License No.       
Operation Completed: Hour 9:30 A Day 20 Month 5 Year 1968

The Above well was plugged as follows:

RTD 3431 8 5/8 csg set at 164' cwc 135 sc. Cem. Mat. 100 sc 50-50 poz cem. W/6% gel.  
Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sc cem.  
thru drill pipe. Heavy mud to 150' set cementing plug and displaced 20 sc cement thru  
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base  
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5/24/68  
INV. NO. 4802-W

Signed: [Signature]  
Well Plugging Supervisor