

15-051-01107-0000

KANSAS

Form CP-3
Rev. 6-4-68
RECEIVED
STATE CORPORATION COMMISSION
RCVO
JAN - 8 1979
01-08-79
CONSERVATION DIVISION
Wichita, Kansas

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name Chief Drilling Co.

Complete Address 905 Century Plaza, Wichita, Ks.

Lease Name Lundy Well No. 2

Location SW NE SE Sec. 16 Twp. 11 Rge. (E) (W) 16

County Ellis Total Depth 3460'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Ks. 67524 License No. 683

Operation Completed: Hour 12:45 P Day 5 Month 1 Year 1979

The above well was plugged as follows:

Total Depth 3460' 8 5/8 csg set 270' cwc 175 sk.

5 1/2 csg. set 3430' cw 100 sk cem. Perf. (3055'-3057') & (3184'-3188')

Filled 5 1/2 csg W/sd (3460'-3000') dumped 4 sk cem W/dump bailer. (3000'-2970')

Cutoff & recovered 486' of 5 1/2 csg.

Mixed & pumped down 8 5/8 csg with 10 sk gel & water W/100 lbs hulls -released

plug & capped with 120 sk 50-50 poz 2% & shutin. FPP 300 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Mussen
Well Plugging Supervisor

DATE 1-10-79
INV. NO. 8911-W