

15-051-16295-0006

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name Chief Drlg. Co., Inc.

Complete Address 905 Century Plaza, Wichita, Kansas 67202

Lease Name Craig (SWD) Well No. 12

Location SW NE SW Sec. 16 Twp. 11 Rge. (E) (W) 16

County Ellis Total Depth 3450'

Abandoned Oil Well Gas Well Input Well X SWD Well X D & A

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 12 N. Day 4 Month 11 Year 1978

RECEIVED
STATE CORPORATION COMMISSION
RCUD
NOV - 7 1978
11-07-78
CONSERVATION DIVISION
Wichita, Kansas

The above well was plugged as follows:

Total Depth 3450' 8 5/8 csg set 273' cwc

4 1/2 csg set 3450' cw 150 sk cem.

4 1/2 csg PBTD 3320' with top perf. (2890')

4 1/2 2-stage collar set 1508' GW/200 sk cem. No pipe recovered.

Set 2" tbg at 3010' -circulated 20 sk gel -displaced 70 sk 50-50 poz 2% -pulled 2" tbg

squeezed 4 1/2 csg with 200 lbs hulls & 70 sk 50-50 poz 2% & shutin. FPP 500 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 11-7-78
INV. NO. 8482-6

Signed: Geo Dassy
Well Plugging Supervisor