

~~15-051-01146-0001~~

15-051-01164-00-01

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 21 1961
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Ellis

Location: SE SE SE Sec. 16 Twp. 11 Rge. _____ (E) _____ (W) 16

Name of Field: _____ Total Depth: 3318

I have this date completed supervision of plugging of:

Lease Name: Lundy Well No. 1

Operator's Full Name: White & Fry

Complete Address: 201 Mobil Bldg Wichita, Kansas

Plugging Contractor: Same & Halliburton Cementing Co

Address: same License No. _____

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No X

If yes how long? _____ Reason: _____

Operation Completed: Hour 5:30PM Day 17 Month 7 Year 61

The above-well was plugged as follows:

8 5/8" 996' circulated with cement - 2 1/2" tubing for oil string 3318' top cement on survey 2500' - cut tubing off at 2490' - circulated hole with heavy mudthrough 2 1/2" (40 sax Gel), pulled tubing to 445', displaced 20 sax cement through 2 1/2" at 445', heavy mud to 160', displaced 20 sax cement through 2 1/2" at 160', heavy mud to 35', filled hole with cement 35' to bottom cellar.

Mudding and cementing by Halliburton Cementing Co.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 8/9/61
INV. NO. 3549-W