

15-051-02050-0000

**KANSAS**  
**STATE CORPORATION COMMISSION**  
**CONSERVATION DIVISION AGENT'S REPORT**

**RECEIVED**  
STATE CORPORATION COMMISSION  
RCWO  
DEC 21 1959  
12-21-59  
CONSERVATION DIVISION  
Wichita, Kansas

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Ellis  
Location: NE SW NW Sec. 17 Twp. 11 Rge. 16 (E) (W)  
Name of Field: \_\_\_\_\_ Total Depth: 3393

I have this date completed supervision of plugging of:

Lease Name: Chesney Well No. 4  
Operator's Full Name: Frontier Oil Co  
Complete Address: 580 4th Natl Bk Bldg Wichita, Kans  
Plugging Contractor: Barnes & Sons  
Address: Russell, Kans License No. 9  
Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_  
Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No   
If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 5PM Day 12 Month 12 Year 59

The above well was plugged as follows:  
8 5/8" 1022' circulated with cement - 4 1/2" 3389' with 150 sax cement  
Perforated 3370'.  
Filled with sand to 3360', set 3 sax cement with dump bailer, pulled  
2767' 4 1/2" to 500', circulated hole with heavy mud through 4 1/2" ( 16 sax Gel)  
displaced 20 sax cement through 4 1/2" at 500', heavy mud to 150', displaced  
20 sax cement through 4 1/2" at 150', heavy mud to 35', set bridge and 10 sax  
cement to bottom cellar.  
Mudding and cementing by Sun Cementing Co.

Signed: *Leon Perry*  
Conservation Division Agent

Reviewed: *J. Lewis Brock*  
Field Supervisor

Remarks:

**INVOICED**  
DATE 1/14/60  
INV. NO. 542-w