

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15(148)

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Isern-Schultz Oil & Gas, Inc.

Complete Address P.O. Box, Ellionwood, Ks. 67526

Lease Name Marshall Well No. 5

Location NW NE NE Sec. 25 Twp. 11 Rge. 18 (East) (West)

County Ellis Total Depth 3506'

Abandoned Oil Well XXXX Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Ks. 67525 License No.

Operation Completed: Hour: 2:20 PM Day: 10 Month: May Year: 19 82

Plugging Operations attended by Agent?: All XXXX Part None

The above well was plugged as follows:

8 5/8"-1266' S.P. cuc. w/600 sacks common. 5 1/2" set at 3501' w/150 sacks common
5' of open hole. Plugged bottom w/50' of sand & 5 sacks cement. Shot pipe 1 time
& recoverd 1700'. Ordered 140 sacks 50/50 posmix-4% Gel.-3% Cal.Cl., 19 sacks
Gel., 5 sacks hulls & 8 5/8" plug. Pumped into 8 5/8" S.P. w/pump truck, 4 sacks
hulls, 15 sacks Gel., 70 sacks cement, 4 sacks Gel., 1 sack hulls, released plug
& followed w/70 sacks cement. Maximum pressure 250 pounds.

Amount of Surface Casing: 1266' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
MAY 18 1982
05-18-82
RCWD
CONSERVATION DIVISION
Wichita, Kansas

I hereby state that I was not present while the above well was being plugged, however; to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

INVOICED Signed: _____
Conservation Division Agent

DATE 5-19-82

INV. NO. 190-61

191