

15-051-01719-0000

Form CP-3
Rev. 6-4-68

KANSAS

Y

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 10 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Okmar Oil Company

Complete Address 1130 Wichita Plaza Wichita, Kansas 67202

Lease Name Thurston Well No. 1

Location CWL NE SW Sec. 18 Twp. 11 Rge. (E) (W) 16W

County Ellis Total Depth 3346'

Abandoned Oil Well XXX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 11A Day 7 Month 11 Year 1969

The above well was plugged as follows:

Total Depth 3346' 8 5/8 csg set at 1010 cwc.

5 1/2 csg set at 3338' cw 100 sk cmt.

5 1/2 csg PBTD 3318'

Filled 5 1/2 csg W/sd (3000-3318) Dumped 5 sk cmt W/dump bailer. (2960-3000)

Cutoff and recovered 1585' of 5 1/2 csg.

Mud to 450' set rock bridge (430-450) Dumped 6 yds readymix cmt. (0-430)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 11/10/69

INV. NO. 802-4